Bruhat Bangalore Mahanagara Palike

Office of the Executive Engineer SWD, Mahadevapura Zone BBMP, 9th Floor Jayanagara Shopping Complex 4th Block Jayanagar, Bengaluru-560 011

No: EE/SWD/MDP/Tend/06/2024-25 Date: 10.03.2025

ADDENDUM-1

Project Name : **Construction of Flood Protection Structures to Storm Water Drain including RCC Retaining walls, Water retention Structures, Nature Based Solutions Structures, Culverts and Bridges Under Karnataka Water Security and Resilience Program (KWSRP) With Externally Funded Project [World Bank] In Mahadevapura Constituency Package-05 of Mahadevapura Zone**

Ref :
1. Tender Notification NO: EE/SWD/MDP/Tend/06/2024-25, Dt: 10-03-2025.
2. Tender Number: BBMP/2024-25/OW/WORK_INDENT

******

With respect to above subject, following Corrigendum to the above tender work is issued due to technical reasons.

Section of Tender	Clause / Item No	As published in Tender Documents	As Amended & to be read as
QUALIFICATION CRITERIA	Tender Notification **(clause 3.2 d)**	**Sl No** / **Particulars** / **Quantities** 1 / Earthwork Excavation / 203360.66 Cum 2 / Providing and filling in foundationwith Granite/Trap Broken metal of 100mm / 10387.97Cum 3 / RMC M25 /M30 Grade / 37082.53 Cum 4 / TMT Steel / 2849.84 Tonnes 5 / PCC M10 / 5254.84 Cum	The intending renderer should sub work done certificates for following nature of work executed any one financial year (for continuous period of 12 Months) in last five years, the following minim quantities of work: (usually 80% of peak annual rate of construction) In support of this, the Tenderer sl furnish Work done Certificate mentioning the Executed Quantity one Financial Year duly certified the Competent Authority not be The Rank of Executive Engineer al with the Technical Bid.

Sl No	Particulars	Quantities
1	Earthwork Excavation	203360.66 Cum
2	Providing and filling in foundationwith Granite/Trap Broken metal of 100mm	10387.97Cum
3	RMC M25 /M30 Grade	37082.53 Cum
4	TMT Steel	2849.84 Tonnes
5	PCC M10	5254.84 Cum

The intending renderer should submit work done certificates for the following nature of work executed in any one financial year (for a continuous period of

Section of Tender	Clause / Item No	As published in Tender Documents	As Amended & to be read as
		12 Months) in the last five years, the following minimum quantities of work: (usually 80% of the peak annual rate of construction) In support of this, the Tenderer shall furnish Work done Certificate by mentioning the Executed Quantity in one Financial Year duly certified by the Competent Authority not below The Rank of Executive Engineer along with the Technical Bid.	
BOQ	Code 09	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge **RMC M25 Grade (Open Foundation)**	Ready Mix Concrete (RMC) w Cement & Cementitious Mater Providing and laying in position Re Mixed or Batch Mixed concrete as IS 10262 mix design procedure Cement Concrete works in all types Structures other than Road wo using coarse aggregate and aggregate derived from natu sources, Ordinary Portland Cem (OPC) @ 75% & GGBS @ 2 proportion, admixtures to accelera retard setting of concrete, to impr durability and workability with impairing strength; including pump of concrete to site of laying, curi carriage for all leads; **but includ the cost of centering, shutteri finishing and reinforcement** as direction of the Engineer-in-cha **RMC M25 Grade (Op Foundation)**
BOQ	Code 10	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of	Ready Mix Concrete (RMC) w Cement & Cementitious Mater Providing and laying in position Re Mixed or Batch Mixed concrete as IS 10262 mix design procedure Cement Concrete works in all types Structures other than Road wo using coarse aggregate and aggregate derived from natu sources, Ordinary Portland Cem (OPC) @ 75% & GGBS @ 2 proportion, admixtures to accelera retard setting of concrete, to impr durability and workability with

Section of Tender	Clause / Item No	As published in Tender Documents	As Amended & to be read as
		concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge **RMC M25 Grade (Sub Structure)** with all lead and lift complete as per specifications and as per Directions of Engineer in charge of the Work.	impairing strength; including pump of concrete to site of laying, curi carriage for all leads; **but includ the cost of centering, shutteri finishing and reinforcement** as direction of the Engineer-in-cha **RMC M25 Grade (Sub Structu** with all lead and lift complete as specifications and as per Direction Engineer in charge of the Work.
BOQ	Code 11	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge **RMC M30 Grade (Open Foundation)** with all lead and lift complete as per specifications and as per Directions of Engineer in charge of the Work.	Ready Mix Concrete (RMC) w Cement & Cementitious Mater Providing and laying in position Re Mixed or Batch Mixed concrete as IS 10262 mix design procedure Cement Concrete works in all type Structures other than Road wo using coarse aggregate and aggregate derived from natu sources, Ordinary Portland Cem (OPC) @ 75% & GGBS @ 2 proportion, admixtures to accelera retard setting of concrete, to impr durability and workability with impairing strength; including pump of concrete to site of laying, curi carriage for all leads; **but includ the cost of centering, shutteri finishing and reinforcement** as direction of the Engineer-in-cha **RMC M30 Grade (Op Foundation)** with all lead and complete as per specifications and per Directions of Engineer in cha of the Work.
BOQ	Code 12	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate /	Ready Mix Concrete (RMC) w Cement & Cementitious Mater Providing and laying in position Re Mixed or Batch Mixed concrete as IS 10262 mix design procedure Cement Concrete works in all type Structures other than Road wo using coarse aggregate and aggregate derived from natu sources, Ordinary Portland Cem (OPC) @ 75% & GGBS @ 2

Section of Tender	Clause / Item No	As published in Tender Documents	As Amended & to be read as
		retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge **RMC M30 Grade (Sub Structure)**	proportion, admixtures to accelera retard setting of concrete, to impr durability and workability with impairing strength; including pump of concrete to site of laying, curi carriage for all leads; **but includ the cost of centering, shutteri finishing and reinforcement** as direction of the Engineer-in-cha **RMC M30 Grade (Sub Structure**
BOQ	Code 13	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge **RMC M30 Grade (Solid Slab Super Structure)** with all lead and lift complete as per specifications and as per Directions of Engineer in charge of the Work.	Ready Mix Concrete (RMC) w Cement & Cementitious Mater Providing and laying in position Re Mixed or Batch Mixed concrete as IS 10262 mix design procedure Cement Concrete works in all type Structures other than Road wo using coarse aggregate and aggregate derived from natu sources, Ordinary Portland Cem (OPC) @ 75% & GGBS @ 2 proportion, admixtures to accelera retard setting of concrete, to impr durability and workability with impairing strength; including pump of concrete to site of laying, curi carriage for all leads; **but includ the cost of centering, shutteri finishing and reinforcement** as direction of the Engineer-in-cha **RMC M30 Grade (Solid Slab Su Structure)** with all lead and complete as per specifications and per Directions of Engineer in cha of the Work.

Tender para ref no./Page No	Description as per the Tender Issued	Amended Description in the Tender
Invitation for Tender (IFT)		

Section of Tender	Clause / Item No	As published in Tender Documents	As Amended & to be read as
			The Government of Karnataka (GOK) has applied financing from the World Bank (WB) toward the Karnataka Water Security and Resilience Program (P506272). A Part of this financing will be used for payments under the advertised Tender and resulting Contract(s) named above and is within the Expenditur Framework
ITT 2 Eligibility, Sub para 2.1		Tenderer are not eligible with consistent history of court Litigations/ arbitration wherein decisions against the Employers are ongoing as on 1st April 2024.	Tenderer with consistent history of court Litigations or arbitration or Environmental, or social, or health or safety requirements or regulations wherein decisions against the Employers are ongoing as on 1st April 202 are not eligible
Section 2: Instruction to Tenderer ITT 3 **Qualification of the Tenderer** Sub para 3.7		Statement IV: Environmental and Social Performance Declaration Statement V: Sexual Exploitation and Abuse (SEA) and/or Sexual Harassment (SH) Performance Declaration Statement VI: Sexual Exploitation and Abuse (SEA) and/or Sexual Harassment Performance Declaration for Subcontractors	These statements are appended after the Statement I in the Page X
Section 2: Instruction to Tenderer ITT 31 **Corrupt or Fraudulent Practices**		After 31.2, added 31.3	31.3 The World Bank's Guidelines on Preventing and Combating Fraud and Corruption in Program for Resul Financing dated February 1, 2012 and revised July 10, 2015 (World Bank's ACG for PforR) will be applicable t the this contract as provided at **Special Conditions the Contract Clause 41** incorporated as a Section o the tender/proposal document) and these may also be accessed at *https://www.worldbank.org/en/programs/program-for-results-financing#3* If there is any inconsistency between the definitions of Corrupt and Fraudulent Practices and the World Bank's ACG for PforR, the definitions provided in the World Bank's ACG for PforR will take precedence.
Section 2: Instruction to Tenderer ITT 32		Addition after ITT 31	**32.0 Online Procurement Appeals through KPP:** Any tenderer aggrieved by an order passed by the Tender Accepting Authority may file a online Procurement-related Appeal through the Karnataka Public Procurement Portal regarding (1) the terms of this Tender, (2) the BBMP's decision to exclude a Tenderer from the procurement process before the contract award, or (3) the BBMP's decision to award

Section of Tender	Clause / Item No	As published in Tender Documents	As Amended & to be read as
			contract. The BBMP peruses and disposes the Appeal accordance with Section 16: Appeal of the KTPP Act a The Karnataka Transparency in Public Procurement Rules, CHAPTER - VII APPEALS 29: Appeal (2).
Section 3: **Qualification Information**	A Note added in line with ITT 3.4, after 1.12		**Note:** In line with ITT 3.4: 1 Minimum Qualificatio Criteria (turnover, value of work completed, equipment, personnel and financial resources) to satisfied for award of a contract and aggregate qualification Criteria to be satisfied if the tendere lowest in more than one contract
STATEMENT II:	STATEMENT II: Financial Situation and Performance (Tendere shall submit this documents with help of financial consultants)		STATEMENT II: Financial Situation and Performance (Tenderer shall submit this documents)
STATEMENT	STATEMENT IV: Work Plan and Methodology (l) Management Strategies and Implementation Plans (MSIP) to manage the (ES) risks		(l) Management Strategies and Implementation Pl (MSIP) to manage the (ES) risks Management Strateg and Implementation Plans (MSIP) to manage the (risks (e.g. [*e.g. Traffic Management Plan to ens safety of local communities from construction traf Strategy for obtaining Consents/Permits prior to start of relevant works; labor influx management pla manage labor influx into project/site areas*
STATEMENT			Statements are renumbered Statement V: Environmental and Social Performance Declaration Statement VI: Sexual Exploitation and Abuse (SEA) and/or Sexual Harassment (SH) Performance Declaration Statement VII: Sexual Exploitation and Abuse (S and/or Sexual Harassment Performance Declaration Subcontractors
Section 5: **Conditions Of Contract**	After GCC 53. Release from Performance		**Added Appendix 1** of General Conditions of Contract Salient features of major labour and other laws that ar applicable to construction industry in India are given a **S.** | **Name of Laws**

Section of Tender	Clause / Item No	As published in Tender Documents	As Amended & to be read as

No	
1	Workman Compensation Act,1923
2	Payment of Gratuity Act,1972
3	Employees PF and Miscellaneous Provision Act,1952 (since amended)
4	Maternity Benefit Act,1961
5	Sexual Harassment of Woman at the work place(Prevention, Prohibition and Redressal) Act,2013
6	Contract Labour (Regulation and Abolition) Act,1970
7	Minimum Wage Act,1948
8	Payment of Wages Act,1936
9	Equal Remuneration Act,1976
10	Payment of Bonus Act,1965
11	Industrial Disputes Act,1947
12	Industrial Employment (Standing Order) Act,1946
13	Trade Union Act,1926
14	Child Labour(Provision and Regulation)Act,1986
15	Inter-state migrant workmen's (Regulation of employment & conditions of services) Act,1979
16	The Building and Other Construction works (Regulation of Employment and Conditions of service), Act,1996 and the cess Act of 1996
17	Factories Act,1948
18	Bonded Labour system (Abolition) Act,1976
19	Employer's Liability Act,1938
20	The Personal Injuries (Compensation Insurance) Act,1963
21	Prohibition of Employment as Manual Scavengers and their Rehabilitation Act, 2013

F. Special Conditions of Contract	**4.2 Contractor to Construct the Works including protection of environment and assurance of public health and safety, facilitate effective RAP**	**SCC 4.2 Special Condition of the Contract, delet the word 'facilitate effective RAP' after safet** **Contractor to Construct the Works includi protection of environment and assurance of pub health and safety**

Section of Tender	Clause / Item No	As published in Tender Documents	As Amended & to be read as
		4.2.1 The Contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other cause arising because of their methods of operation	**4.2.1** The Contractor shall take all reasonable steps protect the environment on and off the Site and to av damage or nuisance to persons or to property of public or others including those squatters (N titleholders) residing/operating close to these dra (unless due processes are followed in accordance w GoK notification dated 16/10/2024) and nuisance if a resulting from pollution, noise or other cause aris because of their methods of operation.
Section 6: Contract Data	Special Condition of the Contract 4.0 **Contractor to Construct the Works including protection of environment and assurance of public health and safety, facilitate effective RAP**		**Special Condition of the Contract, deleted the word 'facilitate effective RAP' after safety,** 4.0 **Contractor to Construct the Works including protection of environment and assurance of public health and safety**

All other terms & conditions remain unchanged.

Executive Engineer
SWD-Mahadevapura Zone
Bruhat Bengaluru Mahanagara Palike

Copy submitted to:
1. Chief Engineer (SWD) for kind information.
2. Superintending Engineer (SWD) for kind information.
3. Office Copy.